

4060143

299
R

API NUMBER 15- 051-23,156-0000

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW NE , SEC. 31 , T 11 S, R 19 W/E

4290 feet from S section line

2310 feet from E section line ^{ANS} _{KCC}

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name ^{Date} Solomon B7 Well # 7-31

Operator: Ritchie Exploration Inc.

County Ellis 122.88

Name & Address 125 N. Market Suite #1000

Well Total Depth 3781 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 165

Abandoned Oil Well XXXXXXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Co Tools License Number _____

Address _____

Company to plug at: Hour: 8:00AM Day: 18 Month: December Year: 19 90

Plugging proposal received from Pete Fiorini

(company name) Ritchie Exploration Inc. (phone) 316-267-4375

were: Order 300 sxs. 65/35 pos 8%gel and hulls.

Perf. at 1575' and 825' Anhydrite and base of Dakota

Run Tubing to TD to plug.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXXXX Part _____ None _____

Operations Completed: Hour: 10:45AM Day: 18 Month: December Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" to 165', 5 1/2" to 3780'. Run tubing to TD and pmp 100 sxs. 65/35pos 8%gel. Pull tbg. to 1800' and pmp 140 sxs. cement to circ. cement to surface.

Pulled tbg. and sqz. from top with 80 sxs. cement. Max.800# SIP 400#

Tied onto annulus and pmp 10 sxs. cement. Annulus full of cement and pressured up.

Max 200# SIP 150#.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1990

Remarks: Allied Cementing

INVOICED

(If additional description is necessary, use BACK of this report)
CONSERVATION DIVISION
Wichita, Kansas

I (did XXXXXXXXXX observe this plugging.

DATE 2-7-91

Signed Herb Deines
(TECHNICIAN)
Herb Deines

INV. NO. 30580

12-18