

298

4 060139

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION, SW SE SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-21,345-0000
SW SE SE, SEC. 31, T 11 S, R 19 WXE
440 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Dale Solomon Well # 3

Operator: Ritchie Exploration Inc.

County Ellis 121.19

Name & Address 125 N. Market #1000

Well Total Depth 3729 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 123

Abandoned Oil Well XXXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Co Tools License Number _____

Address _____

Company to plug at: Hour: 2:00PM Day: 7 Month: December Year: 19 90

Plugging proposal received from Pete Fiorini

(company name) Ritchie Exploration In.c (phone) 316-267-4375

were: Order 320+ sxs, 65/35pos 8%gel

Cleanout and run tubing to TD.

Casing bad and ate up from 600-2295'

Production casing at surface in poor condition.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXX Part _____ None _____

Operations Completed: Hour: 5:45PM Day: 7 Month: December Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" to 123', 5 1/2" to 3728' Run tubing to TD and pmp. 150 sxs.
65/35 pos 8%gel. Pull tbg. to top of cement and pump cement to circ to surface. Circ.

cement with 100 sxs. cement additional. Pulled tubing and tied onto annulus and pmped
70 sxs. cement. Max 500# SIP50#. Tied onto casing and pumped 35 sxs. cement to casing

bad and could not develop any pressure. Checked cement top 12-16-90 and filled with
10 sxs. cement.

Remarks: Allied Cementing.

(If additional description is necessary, use BACK of this form.)

I (did ~~XXXXXX~~ observe this plugging.

DATE 2-7-91

Signed [Signature]
(TECHNICIAN)

INV. NO. 30579

12-7

Herb Deines

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
DEC 16 1990

[Signature]