

4 060140

329
P

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-21,279-0000

SE SE SEC. 31 T 11 S, R 19 W/E

440 feet from S section line

440 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Dale Solomon Well # 1

Operator: Ritchie Exploration Inc.

County Ellis 120.44

Name & Address 125 N. Market Suite #1000

Well Total Depth 3706 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 130

Abandoned Oil Well XXXXXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor _____ Co Tools _____ License Number _____

Address _____

Company to plug at: Hour: 3:30PM Day: 11 Month: December Year: 19 90

Plugging proposal received from Pete Fiorini

(company name) Ritchie Exploration Inc. (phone) 316-267-4375

were: Order 100 sxs. Common and 145+ sxs. 65/35pos 8%gel.

Clean out junk in hole to minimum of 1280'. Casing bad at surface and downhole.

Ran tubing to 1280' to plug.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXX Part _____ None _____

Operations Completed: Hour: 6:45PM Day: 11 Month: December Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" to 130", 4 1/2" to 3700". Run tubing to 1280' and pmp.

100 sxs. Common cement. Pull tubing to 980' and pmp. 65 sxs. 65/35 pos 8%gel to circ.

cement to surface. Pull tubing and tie onto casing. Pmp 60 sxs. cement. Max 900#

SIP 600#, Tie onto annulus and pmp 20 sxs; cement. No pressure due to bad head on csg.

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1990

Remarks: Allied Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 18 1991

INV. NO. 30532

12-11

Herb

Signed Herb Deines
(TECHNICIAN)

Herb Deines