

4-062619

4-8

65
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-21,343-0000

SE NE SW /4 SEC. 31, 11 S, 19 W
4290 feet from S section line
2970 feet from E section line

Operator license# 4767

Lease Solomon "A-P" well # 2

Operator: Ritchie Exploration, Inc.

County Ellis

Address: 125 N. Market
Suite 1000
Wichita, Kansas 67202

Well total depth 3700 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 130 feet

120.25

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Box 347, Chase, Kansas 67524

Company to plug at: Hour: 9:00A.M. Day: 8 Month: April Year: 92

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2943

Were: Order 350 sks. of 60/40 pozmix - 8% gel. - 5 sks. hulls.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 20 1992

Plugging Proposal Received by: Gilbert G. Scheck
Plugging operations attended by agent? All[], Part[], None[]
CONSERVATION DIVISION
WICHITA, KS

Completed: Hour: 3:00P.M., Day: 8, Month: April, Year: 92

Actual plugging report: 8 5/8" @ 130' w/110 sks. 4 1/2" @ 3692'
w/175 sks. Top perf. @ 8' open hole. Plugged bottom with sand and 5
sk. cement to 3500'. Shot pipe 4 times and recovered 2300'. Pump in
4 1/2" casing and circulated cement from 1400' to surface. Hooked on to
8 5/8" and squeezed to 500 P.S.I. Pulled all casing and used 350 sks.
cement. Spotted at 2600' - 2500' - 2400' - 2300' with 25 sks. on all plugs.
Max. pressure on 4 1/2" - 500 P.S.I. Shut in @ 300 P.S.I.
Total sack 350 cement.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES 1408 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2055 GL

I did / did not observe the plugging.

Gilbert G. Scheck

DATE 4-28-92

(agent)

INV. NO. 35088

Form CP-2/3

INVOICED

HD