

15-135-20891-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Palamin Petroleum
Complete Address 394 Insurance Bldg., Wichita, Kansas
Lease Name Brandt Well No. 1
Location C. N/2 NW NW Sec. 2 Twp. 19 Rge. (E) (W) 24
County Ness Total Depth 4367'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX
Other well as hereafter indicated _____
Plugging Contractor H-30 Drlg.
Address Wichita, Kansas License No. _____
Operation Completed: Hour 2:35 A Day 3 Month 6 Year 1974

The above well was plugged as follows:

RTD 4367' 8 5/8 csg set at 244' cwc 150 sk. Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 250' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Massey
Well Plugging Supervisor

INVOICED

DATE 6/5/74
INV. NO. 9245-W