

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Hummon Oil, Inc.,

Complete Address: 821 Union National Bldg., Wichita, Kansas

Lease Name Jensem Well No. 1

Location SW NE SE Sec. 34 Twp. 11 Rge. 19 (E) (W)

County Ellis Total Depth 3678

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Burt Drlg

Address: Great Bend, Kansas License No. _____

Operation Completed: Hour 5:30 P Day 31 Month 5 Year 1968

The Above well was plugged as follows:

RTD 3678' 8 5/8 csg set at 201' cwc 135 sc. Cem. Mat. 100 sc 50-50 poz cem. W/6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cement
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 6/4/68

INV. NO. 4896-u