

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,720-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Green Oil Co.

Complete Address Box 503 Hays, Ks. 67601

Lease Name Jensen

Well No. #3

Location NE SE NW

Sec. 34 Twp. 11 Rge. 19 (East) West

County Ellis

Total Depth 3675'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling Inc.

Address 801 Union Center, Wichita, Ks. 67202

License No. \_\_\_\_\_

Operation Completed: Hour: 5:00 PM Day: 29 Month: Dec. Year: 19 81

Plugging Operations attended by Agent?: All  Part  None XXX

The above well was plugged as follows:

8 5/8"-260' S.P. cuc. w/190 sacks common-2% Gel- 3% Cal. Cl. ~~XXXXXXXXXX~~

Ordered 130 sacks 50/50 posmix-4% Gel- 3% Cal.Cl.&8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 260' w/40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks cement in rat hole.

Amount of Surface Casing: 260' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

**INVOICED**

Signed: \_\_\_\_\_

Conservation Division Agent

DATE 1-19-82

INV. NO. 8924-W

## INVOICE and WELL PLUGGING AUTHORITY

January 19, 1982

INVOICE NUMBER: 8924-W

TO: Green Oil Co.

Box 503

Hays, Ks 67601

## PLUGGING ASSESSMENT AS FOLLOWS:

PAVABLE UPON RECEIPT

Jensen #3

NE SE NW Sec 34-11 19W

Ellis

3675'

\$119.47

NOTE: We also need the following before our file is completed:


- Well Plugging Record (CP-4)  
 Well Log  
 Well Plugging Application (CP-1)

## WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



Administrator

Mr. Gilbert Scheck, 2202 Canterbury Rd., Hays, KS., 67601, (913)628-2600

is hereby assigned to supervise the plugging of the above mentioned well.