

RECEIVED
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

MAR 1 1982

CONSERVATION DIVISION AGENT REPORT

CONSERVATION DIVISION
Wichita, Kansas

API Number 15-051-22851-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Green Oil Operation

Complete Address P.O. Box 503, Hays, Ks. 67601

Lease Name Jenson "A"

Well No. 1

Location 100' NE of NW SW

Sec. 34 Twp. 11 Rge. 19 (East) (West)

County Ellis

Total Depth 3675'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated _____

Plugging Contractor Big Springs Drilling, Inc.

Address Box 8287 Munger Sta, 400 N. Woodlawn, 29, Wichita, Ks. License No. 67208

Operation Completed: Hour: 9:30 AM Day: 26 Month: Feb. Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part _____ None _____

The above well was plugged as follows:

8 5/8"-274' S.P. Cuc. W/ 175 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. and 8 5/8" plug.

Spot W/ drill stem W/ heavy mud between all plugs.

1st plug @ 780' W/ 70 sacks cement

2nd plug @ 270' W/ 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 274' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. ~~A full account for my not being present is as follows:~~

Signed: _____
Conservation Division Agent

INVOICED

DATE 3-2-82

INV. NO. 95-28-W

INVOICE and WELL PLUGGING AUTHORITY

March 2, 1982INVOICE NUMBER: 9528-WTO: Green Oil OperationsP.O. Box 503Hays, KS 67601]

PLUGGING ASSESSMENT AS FOLLOWS:

PAYABLE UPON RECEIPT

Jenson "A" #1

100' NE of NW SW Sec. 34-11-19W

Ellis

3675'

\$119.44

NOTE: We also need the following before our file is completed:


- Well Plugging Record (CP-4)
 Well Log
 Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.


 Administrator

Mr. Gilbert Scheck, 2202 Canterbury Rd., Hays, KS., 67601, (913)628-2600

is hereby assigned to supervise the plugging of the above mentioned well.