

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 59-6

LOCATION NW NE SE

SEC. 34 TWP. 11 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. A-1 Lease Jensen

Operator Skelly Oil Co Address Hutchinson, Kans

Field _____ County Ellis

Total Depth 3676 Feet.

Plugging Contractor Ace Pipe Pulling & Halliburton Co

Plugging Contractor's License No. 2

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1444' circulated with cement - 5 1/2" at 3657'

Perforated at 3652' - Filled with sand to 3640', set

4 sax cement with dump bailer - pulled 2850' 5 1/2" - pumped

hole full mud (35 sax Aquagel), 1/2 pumped cementing plug

to 230', followed by 75 sax cement - cement 230' to 0'.

Mudding and cementing by Halliburton Co - 400# pump pressure.

Eden Letty
District Conservation Agent

Date 8-30-54

PLUGGING

FILE SEC 34 T 11 R 19W
BOOK PAGE 29 LINE 6

STATE CORPORATION COMMISSION

SEP - 1 1954

CONSERVATION DIVISION
Wichita, Kansas