

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
00031 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location: NE NW SW Sec. 34 Twp. 11 Rge. 19 (E) _____ (W) _____
Name of Field: _____ Total Depth: 3649

I have this date completed supervision of plugging of:

Lease Name: Ester Jensen Well No. 1
Operator's Full Name: Skelly Oil Co
Complete Address: 212 Wolcott Bldg Hutchinson, Kans
Plugging Contractor: Ace Pipe Pulling Co
Address: Great Bend, Kans License No. 2
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 24 Month 9 Year 60

The above well was plugged as follows:

8 5/8" 1418' circulated with cement - 5 1/2" 3645' with 250 sax cement -
Baker plugs to 3114' - perforated 3102'.

Filled with sand to 2950', set 4 sax cement with dump bailer, pulled
2450' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" at 600',
(17 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy mud
to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to
35', set rock and filled to bottom cellar with cement.

Mudding and cementing by Halliburton Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 10/13/60
INV. NO. 2034-W