

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 1-4

LOCATION NW NW NW

SEC. 34 TWP. 11 RGE. 19

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Jensen

Operator Skelly Oil Co Address Hutchinson, Kans

Field Solomon County Ellis

Total Depth 3630 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 305' circulated with 150 sax cement. Circulated hole with
mud. Spotted 25 sax cement on bottom through drill pipe,
Set cementing plug at 277' and spotted 25 sax cement
through drill pipe at 277', mud to 75', set cementing
plug and filled hole to surface with 25 sax cement.
These plugs slipped, found top of cement at 150', pumped
in 50 more sacks cement filling hole to bottom cellar
Cementing by Halliburton co.

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1952
CONSERVATION DIVISION
Wichita, Kansas

Jedon Perry
District Conservation Agent

Date 3-15-52

PLUGGING
FILE SEC 34 T 11 R 19W
PAGE 1 LINE 4