

15-135-20263-0000

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 7 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg. Co.

Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Ks.

Lease Name: Goodman "A" Well No. 1

Location: C SW SW Sec. 22 Twp. 19 Rge. 23 (E)(W) XX

County: Ness Total Depth 4375' Oil Well

Gas Well    Input Well    SWD Well    D & A XX Lost Hole   

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace  
30 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls  
and 10 sk cmt to base of cellar. Plug rat hole with 2 sk cmt.

Very truly yours,

Leo F. Murray  
 Conservation Division Agent