

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sharpe of Barnett Oil Co. has this
date requested permission to plug the following described well:

Mr. Sharpe guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Co.

Complete Address: 411 First Nat'l Bk. Bldg., Wichita, Ks.

Lease Name: Dugan Well No. 1

Location: C NW NW Sec. 19 Twp. 19 Rge. 23 (E)(W) X

County: Ness Total Depth 4417 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sharpe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
50 sc cement thru drill pipe. Heavy mud to 225' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Ben F. Messer
Conservation Division Agent