

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Howard Cain of Strata Drilling, Incorporated has this
date requested permission to plug the following described well:Mr. Cain guarantees payment of the plugging fee.Operator's full Name: Strata Drilling, Incorporated,Complete Address: 2421 10th Street, Box #342, Great Bend, Kansas.Lease Name: Beardslee Well No. 1Location: CNE-SW Sec. 27 Twp. 19 Rge. (E)(W) 19 ^{23W}County: Ness Total Depth 4445' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Cain was instructed to plug the well as follows:285'--8 5/8" Surface casing, cement circulated.Circulate hole with heavy mud. Pull DP to 800' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent