



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Lloyd Warren of C + G. Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: C. + G. Drilling Company, Inc.
Complete Address: 340 Broadway, Plaza Bldg. Wichita, ks
Lease Name: Belt 2. Well No. #1
Location: SE-SE-SW Sec. 1 Twp. 20^s Rge. 21^w (E) (W)
County: ness Total Depth: 4440 FT
Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Warren was instructed to plug the well as follows:

8 5/8" 349 FT 50. cu. w/ 200st Cement - 2% Gel. 3% C.C.
Order 105st 50/50 Pozmix 6% Gel + 8 5/8" Plug (2250)
spot with Drill Stem - With Heavy Mud Between all Plugs.
1st Plug @ 720 FT w/ 60st cnt.
2nd Plug @ 360 w/ 30st cnt.
3rd Plug -> solid bridge @ 40 FT w/ 10st cnt.
5th In Cat Hole

Very truly yours, (By allied cnt)
Marion Johnson
Conservation Division Agent
Wichita, Kansas
MAR - 2 1981
CONSERVATION DIVISION
Wichita, Kansas