

1090233

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,628 -00-00

NW NW NW, SEC. 11, T 18 S, R 25 W/E  
4950 feet from ~~NW~~ SE Corner of section line  
4950 feet from ~~NW~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9289

Lease Name Moses Est. Truwell # 1

Operator: Walter Oil and Gas, Inc.  
Name & Address: 240 Main Building, 1212 Main St.  
Houston, TX 77002

County Ness

Well Total Depth 4306 139.95 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_

Address Box 405, Ness City, KS 67560

Company to plug at: Hour: 9:00 am Day: 12 Month: September Year: 19 84

Plugging proposal received from Mack Dugal

(company name) Walter Oil & Gas (phone) 713-659-1221

were: 4 1/2" set at 4296 and cemented to surface Open Hole 4296-4306'

Pump 1 sack hulls, 10 sx cement, 15 sx gel, 20 sx cement, 5 sx gel and 70 sx cement

Plugging Proposal Received by R. Barlittan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:45 pm Day: 12 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4296' and cemented to surface. Open Hole 4296-4306

Pumped 1 sack hulls, 10 sx cement, 15 sx gel, 20 sx cement, 5 sx gel and 70 sx cement.

Maximum pressure 600 psi and shut in pressure 100 psi

Remarks: Used 60/40 Pozmix 22% gel 3% cc by Halliburton  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

(do not observe this plugging.)

INVOICED

Signed R. Barlittan  
(TECHNICIAN)

DATE 9-26-84

INT. NO. 3876

RECEIVED  
STATE CORPORATION COMMISSION  
09-17-1984  
SEP 17 1984