

1 090305

135-22467-0000
API NUMBER 15 - ~~not available~~

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW NW, SEC. 11, T 18 S, R 25 W/E

3300 feet from N/S section line
4620 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Moses Well # 1

Operator: Falcon Exploration, Inc.
Name & Address: 125 North Market, Suite 1531
Wichita, KS 67202

County Ness 140.95

Well Total Depth 4337 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service, Inc. License Number 6907

Address Box 458, Ness City, KS 67560

Company to plug at: Hour: 10:40 am Day: 22 Month: March Year: 19 85

Plugging proposal received from Zack Lewis

(company name) Falcon Exploration, Inc. (phone) 316-262-1378

were: 5 1/2" set at 4336' Perfs at 4325-4331

1st plug sand back to 4275' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:40 am Day: 22 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" wiper plug and pumped 125 sx cement

RECEIVED STATE CORPORATION COMMISSION

MAR 28 1985
03-28-1985
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 1150 psi and shut in 700 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 4-3-85

Signed Robert Barburton (TECHNICIAN)

INV. NO. 7501
3-22