

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24127-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 19-19S-23W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: RUMBLE Well Number: 1  
County: NESS Total Vertical Depth: 4460 feet

Operator License No.: 31652  
Op Name: NORSTAR PETROLEUM, INC.  
Address: 5 INVERNESS DRIVE EAST STE 120  
ENGLEWOOD, CO 80112

Conductor Pipe: Size \_\_\_\_\_ feet: \_\_\_\_\_  
Surface Casing: Size 8.625 feet: 226 WITH 140 SX CMT  
Production: Size 4.5 feet: 4458 WITH 100 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2001 11:15 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4330' & 4 SX CMT. 1ST PLUG AT 1600' WITH 10 S GEL & 50 SX CMT. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 230' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/12/2001 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4408'. PERFS AT 4390-97'. SANDED TO 4330' & 4 SX CMT. 1ST PLUG AT 1600' WITH 8 SX GEL - 50 SX CMT - 2 SX GEL. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 230' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2300' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael J Maier  
(TECHNICIAN)

RECEIVED

OCT 16 2001

KCC WICHITA

INVOICED

DATE 10-16-01 OCT 15 2001

INV. NO. 2002060815  
MP

  
Form CP-2/3