

1 070400

SEP 3 1987

API NUMBER 15-135-23,154-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SE, SEC. 36, T 19 S, R 23 W&E

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3423

Lease Name Lehmann Well # 1

Operator: Cibola Resources Corporation
Name &

County Ness 144.79

Address P.O. Box 7805
Amarillo, TX 79109

Well Total Depth 4455 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 3 Month: 9 Year: 19 87

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie Drilling, Inc. (phone) 316-793-8186

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2267'
Anhydrite 1522-61'

1st plug at 1560' with 50 sx cement, 2nd plug at 900' with 70 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:45 p.m. Day: 3 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement,

2nd plug at 900' with 70 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 0 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

(If you observe this plugging.)

INVOICED

Signed Dan Gordon
(TECHNICIAN)

DATE SEP 1 1 1987

INV. NO. 18074

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 8 14 87 month day year

API Number 15-135-23,154-000

OPERATOR: License # 3423
Name Cibola Resources Corporation
Address P.O. Box 7805
City/State/Zip Amarillo, TX 79109
Contact Person Jack L. Partridge
Phone 316 262-1841

C. SW. SE. Sec. 36 Twp. 19 S. Rg. 23 X West
660' Ft. from South Line of Section
1980 Ft. from East Line of Section
(Notes: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State 801 union center Wichita, KS

Nearest lease or unit boundary line 560' feet
County Ness
Lease Name Lehmann Well # 1
Ground surface elevation feet MSL
Domestic well within 550 feet yes X no
Municipal well within one mile yes X no
Surface pipe by Alternate 1 X
Depth to bottom of fresh water 250'
Depth to bottom of usable water Dakota 1550'
Surface pipe planned to be set 350'
Projected Total Depth 4650' feet
Formation Miss.

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing
Date Aug 7, 1987 Signature of Operator or Agent Jack L. Partridge Title Vice-President

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X
This Authorization Expires 2-10-88 Approved By Pat B. 10-87

set 350' of 8 3/8 on 8/27/87 R.L.
will call back for plug proposal
PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1550' feet depth with 25-30 sxs of 60-40 pos, 6% gel, 3% cc
2nd plug @ Base Dakota feet depth with 80-100 sxs of 60-40 pos, 6% gel, 3% cc
3rd plug @ 400' feet depth with 40-50 sxs of 60-40 pos, 6% gel, 3% cc
4th plug @ 40' feet depth with 10 sxs of 60-40 pos, 6% gel, 3% cc
5th plug @ feet depth with sxs of
(2) Rathole with 10-15 sxs (b) Mousehole with sxs

PUSHER Wilmer Drilling
TD FORMATION
SURFACE PIPE 8 3/8 @ 369
ANHYDRITE 15-12-67 ELEVATION
STARTING TIME & DATE
COMPLETION TIME & DATE
1st PLUG @ 1560 FT. W/ 90 SX
2nd PLUG @ 900 FT. W/ 20 SX
3rd PLUG @ 390 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY
TECHNICIAN

60/40 @ 9091
RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1987
CONSERVATION DIVISION
Wichita, Kansas