

1 031447 3-21

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
138 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-23,987-0000
40' E of
C NE NE, SEC. 35, T 19 S, R 23 W/X
660 feet from NX section line
620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 32039
Operator: Richard W. Thompson, Inc.
Name & Address: 2310 Ohio Drive, Ste. 221
Plano, TX 75093

Lease Name Treloggen Well # 1
County Ness 144.75
Well Total Depth 4454 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 326

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address 401 E. Douglas, Ste. 500, Wichita, KS 67201-8848

Company to plug at: Hour: 1 a.m. Day: 21 Month: 3 Year: 19 97

Plugging proposal received from Bob Kasper
(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1586'
1st plug at 1590' with 50 sx cement, 2nd plug at 740' with 20 sx cement,
3rd plug at 330' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3 a.m. Day: 21 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement,
2nd plug at 740' with 20 sx cement,
3rd plug at 330' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 24 1997
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel 1/2# floSeal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(XXX) did not observe this plugging.

DATE 3-26-97

INV. NO. 47824

Signed Steve Durrant (TECHNICIAN)

3-21 MAY 21 1997

EFFECTIVE DATE: 3-12-97

State of Kansas 135-23,987-0000

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

DISTRICT # 1
SGA? Yes. X No

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 3 14 97
month day year

Spot 40' East of
C NE NE Sec 35 Twp 19 S, Rg 23 West

OPERATOR: License # 32039
Name: Richard W. Thompson, Inc.
Address: 2310 Ohio Drive - Suite 221
City/State/Zip: Plano, Texas 75093
Contact Person: Richard W. Thompson
Phone: (972) 985-3672

660 feet from South North line of Section
620 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Ness
Lease Name: Treloggen Well #: 1
Field Name: None

CONTRACTOR: License #: 5420
Name: White & Ellis Drilling, Inc.

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Mississippi

Nearest lease or unit boundary: 620'

Ground Surface Elevation: 2298' feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 280'

Depth to bottom of usable water: 700'

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 320'

Length of Conductor pipe required: None

Projected Total Depth: 4,500'

Formation at Total Depth: Mississippi

Water Source for Drilling Operations:

well farm pond X other

Well Drilled For: Well Class: Type Equipment:

- X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other

If OWWO: old well information as follows:

Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth:

Bottom Hole Location:

Will Cores Be Taken? yes X no

If yes, proposed zone:

300' Alt. II Req.

Exp. 9/7/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

Pusher Bob Casper - INIT: MM
SPUD DATE 3-12-97 LENGTH SURFACE PLANNED 320ft
RESERVE PIT STATUS- REMOVE FLUID LINED
RATHOLE AHEAD? Y N SIZE HOLE
SURFACE PIPE 1 1/2 @ 326 CONDUCTOR
ANHYDRITE T-1586 B- ELEVATION
TD 4454 FORMATION MASS
RAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX Y N SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1590 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1 1/2, 1/2 Plug @ 140 Ft. W/ 20 SX
Bottom surface @ 24 1997 Ft. W/ 40 SX
40' Plug @ Ft. W/ 10 SX
RAT HOLE CIRC @ SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond X)
TECHNICIAN SD DATE 23-17-97 Hauling
TYPE OF CEMENT 60/40 6% gas 4 4F low sand
STARTING TIME 1:00 (AM/PM) DATE 3-21-97
COMPLETION TIME 3:00 (AM/PM) DATE 3-21-97
CEMENT COMPANY Allval