

1 070269

Plyd. 12-18-86

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,083-0000  
NW NE NE, SEC. 5, T 19 S, R 24 W/E  
4950 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Harkness Well # 1

Operator: Berexco Inc.

County Ness

Name & Address 970 Fourth Financial Center

Well Total Depth 4435 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Beredco Inc. License Number 5147

Address 401 E. Douglas, #402, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 18 Month: 12 Year: 19 86

Plugging proposal received from Howard Cain

(company name) Beredco Inc. (phone) 316-653-2463

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2348'  
Anhydrite 1635-70'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 800' with 70 sx cement,

3rd plug at 30' below base of surface pipe with 40 sx cement,

4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Don Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 18 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1670' with 50 sx cement,

2nd plug at 850' with 70 sx cement,

3rd plug at 290' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

**INVOICED** STATE CORPORATION COMMISSION

DATE 12-30-86 DEC 23 1986

Signed Don Jordan  
(TECHNICIAN)

INV. NO. 15670  
12-18 CONSERVATION DIVISION  
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12 11 86 month day year 1:49

API Number 15- 135-23,083-0000

OPERATOR: License # 5363 Name BERESEXO INC. Address 970 Fourth Financial Center Wichita, Kansas 67202 Contact Person Evan Mayhew Phone (316) 265-3311

NW NE NE Sec. 5 Twp. 19 S, Rg. 24 4950 990 Ft. from South Line of Section Ft. from East Line of Section

CONTRACTOR: License # 5147 Name BEREDCO INC. City/State Wichita, Kansas

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County Ness Lease Name Harkness Well # 1 Ground surface elevation 2348 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Ext. Air Rotary OWWO Expl Wildcat Cable

Depth to bottom of fresh water 100 Depth to bottom of usable water 950 850 Surface pipe by Alternate: 250 Surface pipe planned to be set 250 Conductor pipe required Projected Total Depth 4450 feet Formation Mississippian

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 12-9-86 Signature of Operator or Agent Title

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 6-10-87 Approved By 12-10-86

SPUD - 12-11-86

SA = [Signature]

NW NE NE Sec. 5 Twp. 19 S, Rg. 24 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug #, Depth (ft), SXS, and SXS description. Includes handwritten notes like 'Base Anhyd 1600' and '30' below top'.

STATE CORPORATION COMMISSION (2) Rathole with

DEC 23 1986

CONSERVATION DIVISION Wichita, Kansas

Table with 4 columns: Formation, Surface Pipe, Anhydrite, Starting Time & Date, Completion Time & Date, Plug #, FT. W/, SXS, Rat Hole, Mouse Hole, Water Well Plugged, Cement Company, Technician, and SXS description.

Howard-Cain

FORMATION N/A

SURFACE PIPE 8 5/8" @ 259'

ANHYDRITE 1635'-70' ELEVATION 2348'

STARTING TIME & DATE 12-18-86, 12:30PM

COMPLETION TIME & DATE 12-18-86, 2:00PM

1st PLUG @ 1670 FT. W/ 50 SXS

2nd PLUG @ 850 FT. W/ 70 SXS

3rd PLUG @ 290 FT. W/ 40 SXS

4th PLUG @ 40 FT. W/ 10 SXS

RAT HOLE CIRCULATED W/ 15 SXS

MOUSE HOLE CIRCULATED W/ 10 SXS

WATER WELL PLUGGED W/ SXS

CEMENT COMPANY B. J. Titan

TECHNICIAN Dan Goodrow, SWSM

60/40 pr. 670gel 370CC