

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24162-00-00
Spot: SESESE Sec/Twnshp/Rge: 11-19S-24W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: SHRAMEK TRUST Well Number: 1
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 9971
Op Name: KODIAK PETROLEUM, INC.
Address: PO BOX 4677
ENGLEWOOD, CO 80155

Conductor Pipe: Size feet: 8/43.00
Surface Casing: Size 8.625 feet: 347
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 10/01/2001 6:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 40-0' WITH CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/01/2001 8:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 40-0' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

OCT 05 2001
KCC WICHITA

Signed Steve Durrant
(TECHNICIAN)

INVOICED

OCT 04 2001

DATE 10-05-01

INV. NO. 2002060743