

1 060584

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,835-0000 *R*

SE NE SE, SEC. 3, T 19 S, R 24 W/E

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name McDonald Well # 1-F

Operator: Pickrell Drilling Company

County Ness *141.87*

Name & Address 110 North Market, Suite 205

Well Total Depth 4365 feet (Mississippi)

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 12 Month: June Year: 19 85

Plugging proposal received from Gary Christopher

(company name) Pickrell (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2315' Anhydrite 1575'

1st plug at 1600' with 50 sx cement

2nd plug at 800' with 50 sx cement

3rd plug at 280' with 50 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:45 am Day: 12 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1660' with 50 sx cement, 2nd plug at 820' with 70 sx

cement, 3rd plug at 300' with 40 sx cement, 4th & 15th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 17 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

Dan Goodrow went to the location, but did not arrive in time to see plugging. (xxx did not) observe this plugging.

INVOICED

Signed Paul A. Luthi (TECHNICIAN)

DATE 6-20-85

INV. NO. 8642