

To: 1090487 10-14
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,387-0000
C SE NW, SEC. 3, T 19 S, R 24 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30742

Lease Name Kraft Well # 1
County Ness
Well Total Depth 4420 143.65 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 211

Operator: Palomino Petroleum, Inc.
Name & Address 4924 SE 84th
Newton, KS 67114-8827

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:30 a.m. Day: 14 Month: 10 Year: 19 94

Plugging proposal received from Kevin Strube

(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

were: 4 1/2" at 4418' w/210 sx cement, PBDT 4375'; Perfs at 4337-46'
1st plug sand back to 4275' and dump 4 sx cement on top of sand through bailer,
2nd plug perforate casing at 850' and pump in 80 sx cement,
3rd plug shot casing at 500' and pump 20 sx cement, 4th plug at 240' with 40 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 14 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 80 sx cement at 850',

3rd plug pulled to 500' and pumped 20 sx cement,

4th plug pulled to 240' and pumped 40 sx cement,

5th plug at 40' with 10 sx cement. Circulated cement to pit.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 850' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

~~(to be observed)~~ Observe this plugging.

DATE 10-26-94

INV. NO. 41517

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1994
WICHITA, KANSAS