

1050246

KANSAS
ECC

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,121 22421-0000

SW NW NE, SEC. 12, T 17 S, R 26 W ~~XX~~

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Stutz "H" Well # 1

Operator: Pickrell Drilling Company
Name & Address 110 North Market, Suite 205,
Wichita, KS 67202

County Ness

Well Total Depth 4545 147.71 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 am Day: 8 Month: June Year: 19 84

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-692-2506

were: 4 1/2 set at 4532' Perfs 4648-76' PBD 4480'

1st plug sand back to 4410 and dump 4 sx cement on top of sand
pump in sequence 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release

8 5/8" rubber plug and pump an additional 125 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 8 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4532' Perfs 4648-76' PBD 4480'

1st plug sanded back to 4410 and dumped 4 sx cement on top of sand, 2nd plug pumped in
sequence 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released

8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 500 psi and shut in pressure 100 psi

Remarks: Used 50/50 Pozmix 6% gel 3% cc by Allied. They recovered 2500' of 4 1/2"
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-18-84

INV. NO. 2065
6-8

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1984

Signed Richard W. Lacey
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas