

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-135-23,401-0000

LEASE NAME Pfannenstiel "N"

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

3630 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 2 TWP. 19S RGE. 24 ~~05W~~ (W)

COUNTY Ness

Date Well Completed 11-11-89

Plugging Commenced 11-11-89

Plugging Completed 11-11-89

LEASE OPERATOR Kiwanda Energy, Inc.

ADDRESS P. O. Box 1329, Wichita, KS 67201

PHONE#(316) 267-2697 OPERATORS LICENSE NO. 9121

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-11-89 (date)

by State Plugger, Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	207'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set. Circulate heavy mud in hole. 1st plug from 1580' to 1380' w/50 sx. 2nd plug from 780' to 460' w/80 sx. 3rd plug from 207' to 47' w/40 sx. 4th plug from 40' SB to surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kiwanda Energy, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) of Operator Commission

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton  
150 N. Main, Suite 801

(Address) Wichita, KS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 WICHITA, KANSAS  
 11-11-89

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 89

Sharan J. Branstetter  
 Sharan J. Branstetter Notary Public

My Commission Expires: May 18, 1993

