


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 2 Twp. 19S Rge. 24 (E) W (W)

Location as "NE/CNW4SW4" or footage from lines SE/4 SE/4 SE/4

Lease Owner Operator: Hellar Drilling Company, Inc.

Lease Name PFAFF Well No. 1

Office Address Union Center Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 12, 19 61

Application for plugging filed (verbal) December 12, 19 61

Application for plugging approved (verbal) December 12, 19 61

Plugging commenced December 12, 19 61

Plugging completed December 12, 19 61

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well B. Houghton

Producing formation Depth to top Bottom Total Depth of Well 4390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	252'	8-5/8"	252'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole. Bottom plug set at 250' with 25
sacks cement mixed and poured through drill
pipe. Top plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1961
CONSERVATION DIVISION
Wichita, Kansas
12-15-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Birmingham-Bartlett Drilling Co.
Address 300 Kaufman Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., contractor
(employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.

(Signature) By Richard Hindery Partner
300 Kaufman Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 61.

My commission expires October 2, 1962.

Beverly Larson Notary Public.



PFAFF NO. 1 WELL

LOCATION: SE/4 SE/4 SE/4
Section 2-19S-24W
Ness County, Kansas

SPUDDED: 11-30-61
COMPLETED: 12-12-61

OPERATOR: Hellar Drilling Company, Inc.
Union Center Building
Wichita 2, Kansas

CONTRACTOR: Birmingham-Bartlett Drilling Co.
300 Kaufman Building
Wichita 2, Kansas

SURFACE CASING: 8-5/8" casing cemented at 252'
with 160 sacks cement.

OIL STRING: None set. Hole was plugged on
12-12-61.

L O G

(Figures indicate bottom of formation)

0 -	45	Surface Clay
	145	Sand and Shale
	895	Shale and Shells
	905	Anhydrite
	975	Shale
	1210	Sand
	1521	Red Bed and Shale
	1530	Anhydrite
	1600	Shale and Shells
	2025	Shale and Red Bed
	2205	Shale and Shells
	2900	Lime and Shale
	2945	Shale and Shells
	3835	Lime and Shale
	3965	Lime
	4021	Lime and Shale
	4155	Lime
	4200	Shale and Lime
	4245	Lime
	4260	Lime and Shale
	4345	Cherty Conglomerate
	4390	Lime and Shale
	4390	Rotary Total Depth

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the Pfaff No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery
Richard Hindery, Partner

Subscribed and sworn to before me
this 13th day of December, 1961.

Beverly Larson
Beverly Larson, Notary Public
My commission expires October 2, 1962.