


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 1 Twp. 19SRge. 24W E/W-
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C-S/2 S/2 SE/4

Lease Owner Associated Petroleum Consultants
Lease Name Franz Well No. 1
Office Address 645 R.H. Garvey Bldg., Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed June 30, 19 79
Application for plugging filed Verbal Application 19 79
Application for plugging approved Verbal Approval 19 79
Plugging commenced June 30, 19 79
Plugging completed June 30, 19 79
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,350'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,350 ft. (rotary total depth) to 700 ft. Set plug at 700 ft. and cemented with 70 sacks cement. Filled hole with heavy rotary mud from 700 ft. to 246 ft. Set plug at 246 ft. and cemented with 20 sacks cement. Filled hole with heavy rotary mud from 246 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe. RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet) JUL - 6 1979

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530 CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Merle Britting, Agent (copy name of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1979



Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Associated Petroleum Consultants

SEC. 1 T. 19S R. 24W
LOC. C-S/2 S/2 SE/4

FARM Franz NO. 1

COUNTY Ness

ROTARY TOTAL DEPTH 4,350'
COMM. June 20, 1979 COMP. June 30, 1979
CONTRACTOR H-30, Inc. (Rig #2)
ISSUED July 5, 1979

CASING

10 3/4"
8 5/8" Set at 256' cemented w/200 sxs cement
5 1/2"
4 1/2"

ELEVATION 2,265' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	521'
Shale and Sand	1,480'
Shale	1,496'
Anhydrite	1,546'
Sand and Shale	1,950'
Shale	2,170'
Lime and Shale	2,405'
Shale and Lime	2,815'
Lime and Shale	3,174'
Shale and Lime	3,300'
Lime and Shale	3,790'
Lime	3,890'
Lime and Shale	3,995'
Lime	4,125'
Lime and Shale	4,182'
Lime	4,225'
Lime and Shale	4,242'
Lime	4,350'
Rotary Total Depth	4,350'

RECEIVED
STATE CORPORATION COMMISSION

JUL - 6 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.


H-30, INC.

Merle Britting
Merle Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 5th day of July, 1979.

Elsie Willison
Elsie Willison - Notary Public



My Commission Expires:
July 25, 1982