

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis

County. Sec 34 Twp. 11S Rge. 19W (X) (W)

Location as "NE/CNW/SW" or footage from lines NW 1/4 NE 1/4

Lease Owner Artnell Company & Leben Drilling, Inc.

Lease Name Jensen Well No. 1

Office Address 533 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-22-58 19

Application for plugging filed 1-22-58 19

Application for plugging approved 1-22-58 19

Plugging commenced 1-22-58 19

Plugging completed 1-22-58 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	218'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st Plug @ 600' with 20 sacks cement.  
2nd Plug @ 210' with 15 sacks cement.  
Top Plug @ 40' with 10 sacks cement to base of cellar

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 9 1958  
DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin  
905 Central Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 1958

My commission expires June 17, 1961

Ruth N. Benjamin Notary Public.

PLUGGING  
FILE SEC. 34 T. 11 R. 19 W  
BOOK PAGE 79 LINE 8



DRILL LOG

COMPANY: ARTHUR CO. & LEBEN DRILLING, INC.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 WELL: JENSEN #1  
 LOCATION: NW 1/4 NE Sec. 34-11-19W  
 ELLIS COUNTY, KANSAS  
 COMMENCED: 1-11-58  
 COMPLETED: 1-22-58

0	218	Rocks & Shale	
218	785	Shale	
785	1232	Shale, Sand & Red Bed	
1232	1420	Red Bed & Shale	
1420	1465	Anhydrate	TOPS:
1465	1520	Shale & Shells	ANHYDRATE 1480
1520	1715	Shale & Lime	TOPEKA 3120 -999
1715	2435	Shale & Lime	HEBNER 3328 -1199
2435	2615	Lime & Shale	LANSING 3368 -1239
2615	2725	Shale & Lime streaks	EE. A. B. 3599 -1470
2725	3230	Lime & Shale	ARBUCKLE 3670 -1541
3230	3355	Lime & Shale	
3355	3490	Lime	ELEVATION 2129 K.B.
3490	3550	Lime	
3550	3686	Lime	
	3686	<u>Rotary Total Depth - D &amp; A</u>	

Set 218' of 8 5/8" Surface casing with 150 sacks cement and 2% CaO1.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Jensen #1, located NW 1/4 NE of Section 34, Township 11 South, Range 19 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: Frank Hamlin  
 Frank Hamlin

STATE OF KANSAS )  
 COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 29th day of January, 1958.

Ruth N. Benjamin  
 Ruth N. Benjamin, Notary Public

My Commission Expires:  
 June 17, 1961.

PLUGGING  
 FILE SEC 34 T 11 R 19 W  
 BOOK PAGE 79 LINE 8