

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-23,081-0000

LEASE NAME Solomon

TYPE OR PRINT  
NOTICE: Fill out completoly  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER B - P #3

           Ft. from S Section Line

           Ft. from E Section Line

SEC. 31 TWP. 11 RGE. 19W (E) or (W)

COUNTY Ellis

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000 Wichita, KS 67202

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed           

Plugging Commenced 3-7-94

Character of Well Oil

Plugging Completed 3-9-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on            (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached?           

Producing Formation            Depth to Top            Bottom            T.D. 3766'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	172'	none
				5 1/2	3758'	805'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
Sanded bottom to 3642' & 5 sks cement. Shot @ 2241, 1516, & 805 - pipe did not move much.  
Took head off & swedged in. Spotted 150 sks w/200# hulls @ 805'. Pulled to 200', circulated 65 sks w/150# hulls to surface. Pulled rest of pipe. 65/35 poz 10% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6058

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 15th day of March, 1994

Irene Herzberg  
Notary Public

My Commission Expires: 

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 16 1994  
CONSERVATION DIVISION  
Wichita, Kansas

