

DEC 21 1995

CONSERVATION DIVISION
 WICHITA, KS

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Soloman B-P

WELL NUMBER 6

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 31 TWP. 11 RGE. 19 (N) (M) (W)

COUNTY Ellis

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Ste 1000 Wichita, Ks. 67202

PHONE (316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed

Plugging Commenced 12-13-95

Plugging Completed 12-14-95

The plugging proposal was approved on (date)

by Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3798'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	175	none
				5 1/2"	3798'	2124'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3650' and 5 sacks cement. Shot pipe at 2115'. Pulled to 1960', pumped 45 sacks cement and 200# hulls. Pulled to 1580', pumped 45 sacks cement and 100# hulls. Pulled to 775', pumped 40 sacks cement and 100# hulls. Pulled to 225', circulated to surface with 50 sacks cement and 100 hulls. Pulled casing, topped off with 20 sacks cement. (60/40 10% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc. Wichita, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 20th day of December, 1995

Irene Herzberg
 Notary Public

My Commission Expires:
 USE ONLY ONE SIDE OF EACH FORM

