

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-051-23,156-0000  
 Lease Name Solomon B

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 7-31  
4290 Ft. from S Section Line  
2310 Ft. from E Section Line

LEASE OPERATOR Ritchie Exploration, Inc.  
 ADDRESS 125 N. Market, Suite 1000, Wichita, Ks 67202  
 PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

SEC. 31 TWP. 11 RGE. 19 (E) or (W)  
 COUNTY Ellis

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed \_\_\_\_\_  
 Plugging Commenced 12/18/90  
 Plugging Completed 12/18/90

The plugging proposal was approved on 12/18/90 (date)  
 by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation L/KC & Arbuckle Depth to Top 3511' (L/KC) Bottom 3734' (Arb.) 3781'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD | RECEIVED STATE CORPORATION COMMISSION

| Formation | Content | From | To | Size   | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 165'   | -0-        |
|           |         |      |    | 5 1/2" | 3780'  | -0-        |

MAR 15 1991

CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perforated Anhy @ 1575' & Dakota @ 825'. Ran 2" tbg to PBTD @ 3756'. Pumped 100 sx 65/35 Pozmix + 8% gel. Pulled tbg upto 1845'. Pumped 110 sx same cmt. Circ. to surf. Pulled tbg out of hole. Pumped 80 sx same cmt. Sqz to 800# max. Shut in @ 400#; down 5 1/2" csg. Pumped 10 sx same cmt down 8 5/8" csg. Max = 200#. Shut in @ 150#. Plugging complete @ 10:45:am, 12/18/91. Witnessed and approved by Herb Deines.

Name of Plugging Contractor Express Well Service License No. \_\_\_\_\_


Address Victoria, Kansas 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Ellis

A. Scott Ritchie III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
 (Address) 125 N. Market, Suite 1000, Wichita, Ks



AND SWORN TO before me this 14th day of March, 1991

Danna Mchaig  
 Notary Public

My Commission Expires: 9/20/94