


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 31 Twp. 11S Rge. 19 E/W
Location as "NE/CNW1SW1" or footage from lines
440' FWL & 330' FSL NE/4

Lease Owner Don E. Pratt
Lease Name DALE SOLOMON Well No. 9-31
Office Address Box 370, Hays, KS 67601
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Date Well completed October 31 19 78
Application for plugging filed October 31 19 78
Application for plugging approved October 31 19 78
Plugging commenced October 31 19 78
Plugging completed October 31 19 78
Reason for abandonment of well or producing formation
D&A

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3752'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	161'	----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 600' w/70 sx, 50-50 posmix, 6% gel
2nd plug @ 150' w/20 sx, 50-50 posmix, 6% gel
3rd plug @ 40' w/10 sx, 50-50 posmix, 6% gel

NOV 17 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Wm. S. Shropshire of Murfin Drilling Company (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God

(Signature) *Wm. S. Shropshire*
Wm. S. Shropshire, Asst. Gen. Mgr.
617 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1978

My commission expires

KERRAN LIDIA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. Feb. 6, 1982

Kerran Lidia
Kerran Lidia Notary Public.


WELL LOG

COMPANY Don E. Pratt
FARM DALE SOLOMON NO. 9-31

SEC. 31 T. 11S R. 19W
LOC. 440' FWL & 330' FSL NE/4

RIG. NO. 15
TOTAL DEPTH 3752'
COMM. October 25, 1978 COMP. October 31, 1978

COUNTY Ellis
KANSAS



CONTRACTOR Murfin Drilling Company

CASING
20 10
15 8 -5/8" @ 161' w/125 sx.
12 6
13 5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

161'	Surface soils, clay & Shale
980'	Shale, Shells & Sand
1190'	Sand
1215'	Shale
1504'	Shale & Red Beds
1550'	Anhydrite
2350'	Shale
3320'	Shale & Lime
3445'	Lime & Shale
3752'	Lime RTD

RECEIVED
STATE CORPORATIONS COMMISSION
NOV 17 1978
CONSERVATION DIVISION
Topeka, Kansas

State of KANSAS
County of SEDGWICK } ss:

I, Wm. S. Shropshire of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the DALE SOLOMON #9-31 well.

Wm. S. Shropshire
Wm. S. Shropshire, Asst. Gen. Mgr.

Subscribed and sworn to before me this 15th day of November 19 78

My Commission Expires:

KERRAN LIDIA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. Feb. 6, 1982

Kerran Lidia
NOTARY PUBLIC
Kerran Lidia