

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21,345-0000

LEASE NAME Solomon A-P

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3

440' Ft. from S Section Line

1320' Ft. from E Section Line

LEASE OPERATOR Ritchie Exploration, Inc.

SEC. 31 TWP. 11 RGE. 19 (E) or (W)

ADDRESS 125 N. Market, Suite 1000, Wichita, Ks 67202

COUNTY Ellis

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed _____

Character of Well Oil

Plugging Commenced 12/07/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/07/90

The plugging proposal was approved on 12/07/90 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation L/KC & Arbuckle Depth to Top L/KC 3493' Arb. Bottom 3741' T.D. 3729'

Show depth and thickness of all water, oil and gas formations. 3741' (OHTD)

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COM.

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	123'	-0-
				5 1/2"	3728'	-0-

MAR 15 1991

03-15-91

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Numerous csg holes from 600'-2295'. Ran 2" tbg to 3730'. Pumped 150 sx 65/35 pozmix + 8% gel. Pulled tbg up to 1008'. Pumped 100 sx same cmt. circ. to surf. Pulled tbg out of hole. Pumped 70 sx same cmt down 8 5/8" csg. Max=500#, shut in @ 50#. Pumped 35 sx same cmt down 5 1/2" csg. No PSI due to poor csg at surf. Plugging complete @ 5:45 pm, 12/07/90. Note: 12/11/90 - loaded 5 1/2" casing with 10 sx same cement to surface.

Name of Plugging Contractor Express Well Service License No. _____

Address Victoria, Kansas 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

A. Scott Ritchie III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) 125 N. Market, Ste. 1000, Wichita, Ks

DANNA MCKAIGS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 9/20/94

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1991

Danna Mckaig
Notary Public

My Commission Expires: 9/20/94