

15-135-20285-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1970
CONSERVATION DIVISION
Wichita, Kansas

10-22-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beardmore Oil, Inc.
Complete Address 700 One Twenty Bldg., Wichita, Kansas
Lease Name Schlegal "C" Well No. 1
Location SE NW Sec. 36 Twp. 19 Rge. (E) (W) 25
County Ness Total Depth 4417'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Pipe Pullers, Inc.
Address Box 486 Great Bend, Kans.,s License No. 462
Operation Completed: Hour 3 P Day 19 Month 10 Year 1970

The above well was plugged as follows:

Total Depth 4417' 8 5/8 csg set at 546' cwc 275 sk.
5 1/2 csg set at 4406' cw 175 sk cmt.
Filled 5 1/2 csg W/sd (4390-4417) Dumped 5 sk cmt W/dump bailer. (4350-4390)
Recovered 2818' of 5 1/2 csg.
Set plug at 500' rock and sand to 475'. Dumped 5 sk cmt W/dump bailer.
Baled hole dry to 325' hit bridge of cement.
Dumped 4 1/2 yds readymix cmt (0-325)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 10-22-70

INV. NO. 2735-W