

15-135-00773-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUL 2 1973
07-02-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Delta Western Co.

Complete Address 1223 Union-National Bldg., Wichita, Kansas

Lease Name Dinges Well No. 1

Location C NW NW Sec. 22 Twp. 19 Rge. 25W(1) (W) 2

County Ness Total Depth 4560'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones Drlg, Inc.

Address Wichita, Kansas License No.

Operation Completed: Hour 6:15 P Day 29 Month 6 Year 1973

The above well was plugged as follows:

RTD 4560' 8 5/8 csg set at 391' cwc 225 sk. Cmt. Mat. 50-50 poz W/4% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Res F. Massey
Well Plugging Supervisor

DATE 7/2/73
INV. NO. 7548-W