

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Nadel & Gussman

Complete Address: 1714 1st Natl Bk Bldg Tulsa, Okla

Lease Name Lynn Well No. 2

Location SW SE SE Sec. 14 Twp. 15 Rge. 11 (E) 18 (W)

County Ellis Total Depth 3486

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knighth Casing Pulling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 5PM Day 3 Month 12 Year 64

The Above well was plugged as follows:

8 5/8" 1280' circulated with 800 sax cement - 5 1/2" 3482' with 100 sax cement.

Sanded back to 3470', set 4 sax cement with dump bailer - pulled 2522'  
5 1/2" to 825' - circulated hole with heavy mud through 5 1/2" - ( 27 sax Gel),  
pulled 5 1/2" to 450', displaced 25 sax cement through 5 1/2" at 450', heavy mud  
to 180', displaced 25 sax cement through 5 1/2" at 180', heavy mud to 35',  
cement 35' to 0'.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/9/64

INV. NO. 312-11

Signed: Edson Peety  
Well Plugging Supervisor