

12

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: NE SE SE Sec. 14 Twp. 11 Rge. 18 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3462

I have this date completed supervision of plugging of:

Lease Name: Lynn Well No. 1

Operator's Full Name: Nadel & Gussman

Complete Address: 1714 1st Natl Bk Bldg Tulsa, Oklahoma.

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kansas License No. 49

Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

/ Was any delay in plugging operations caused by Conservation Division Agent? Yes  No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 15 Month 1 Year 61

The above well was plugged as follows:

8 5/8" 1195' circulated with cement - 5 1/2" 3454' with 125 sax cement.

Filled with sand to 3440', set 4 sax cement with dump bailer, pulled

2630' 5 1/2" to 400', circulated hole with heavy mud through 5 1/2" at 400',

(33 sax gel), displaced 25 sax cement through 5 1/2" at 400', heavy mud to

200', displaced 25 sax cement through 5 1/2" at 200', heavy mud to 35', set

bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED

DATE 1/26/61

INV. NO. 2558-u

RECEIVED  
STATE CORPORATION COMMISSION

JAN 20 1961

CONSERVATION DIVISION  
Wichita, Kansas