

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Herman Geo. Kaiser
Complete Address 4120 East 51st St, Tulsa, Kansas 74135
Lease Name Lynn Well No. 2
Location SW NE SE Sec. 14 Twp. 11 Rge. (E) (W) 20
County Ellis Total Depth 3428'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor SW Casing Pulling
Address _____ License No. _____
Operation Completed: Hour 12:30 P Day 30 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 3428' 8 5/8 csg set at 1130' cwc 325 sk 12% gel.
4 1/2 csg set at 3423' cw 100 sk cem.
Filled 4 1/2 csg W/sd (3428-3400) dumped 3 sk cem. W/dump bailer. (3400-3370)
Cutoff & recovered 2820' of 4 1/2 csg.
Filled 8 5/8 csg W/mud to 375' -set rock & sand bridge (375-350)
Filled with RM cem. from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 1/6/75
INV. NO. 579-W