

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1979

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 155-28579-0000 (of this well)

Operator's Full Name F. T. M. OIL COMPANY  
Complete Address 505 UNION CENTER - WICHITA, KANSAS - 67202  
Lease Name BOYD Well No. # 1 - (OWNED)  
Location C - SE - SW Sec. 23 Twp. 19 Rge. 24 (E) (W) W  
County NESS Total Depth 4256 FT.  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor HELSON CHASING PULLING  
Address BOX 176 CHASE, KANS - 67526 License No. 683  
Operation Completed: Hour 1:15 PM Day 9th Month AUG. Year 1979

The above well was plugged as follows:

8 3/8" 287 FT. S.P. CUC. 175 ST. - 5 1/2" T.D 4252  
PERIS - 4 FT. OPEN HOLE - SET PLUG AND SAND TO 4300 FT.  
AND 5 ST. CMT. - SHOT PIPE AT - 2505 FT. RECOVERED - 2505 FT.  
ORDERED 140 ST. 50/50 POZMIX 6% GEL. - 15 ST. GEL. - 3 ST. HULL'S  
AND 8 3/8" PLUG (PUMPED IN WITH PUMP TRUCK)  
PUT IN - 2 ST. HULL'S - 8 ST. GEL - 60 ST. CMT. - 5 ST. GEL  
1 ST. HULL'S - RELEASED PLUG - AND 70 ST. CMT. - PLUG CONTAINER  
BLEW OFF AND LOST APPROX 10 ST. CMT. - MAX PRESSURE - 500 LBS TO 0 LBS

I hereby certify that the above well was plugged as herein stated. CEMENTED BY ALLIED CEMENTING.

INVOICED

Signed: William Schmitt  
Well Plugging Supervisor

DATE 8-13-79  
INV. NO. 0180-W