

15-135-20939-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Mellies "E" Well No. E-1

Location SE-NW-SE Sec. 20 Twp. 19 Rge. (E) (W) 24

County Ness Total Depth 4432'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 8:30 PM Day 23 Month 9 Year 1974

The above well was plugged as follows:

350'--8 5/8" Surface casing, cement circulated.

Circulated hole with heavy mud. Pulled DP to 850' and displaced 80 Sx. cement thru

DP. Pulled DP to 310' and displaced 35 Sx. cement thru DP. Pulled DP, set bridge

@ 40' with 1/2 sack hulls and 15 Sx. cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/1/74

INV. NO. 2-W