

15-135-2898-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Co.  
Complete Address 705 4th Nat'l Bank Bldg., Wichita, Kansas  
Lease Name Antenem "R" Well No. 1  
Location C SE SW Sec. 18 Twp. 19 Rge. (E) (W) 26  
County Ness Total Depth 4635'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor        Co. Tools         
Address        License No.       

Operation Completed: Hour 6:30 P Day 8 Month 7 Year 1974

The above well was plugged as follows:         
RTD 4635' 8 5/8 csg set at 230' cwc 160 sk. Cmt Mat 50-50 poz 6% total gel.  
Gunnedpits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 7/11/74  
INV. NO. 9507-W