

15-135-00664-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Kern - Landes Oil
Complete Address: Box 107 Liberal, Kansas
Lease Name Pember Well No. 1
Location CNE SW Sec. 3 Twp. 19 Rge. (E) (W) 26
County Ness Total Depth 4541
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Hellar Drg Co
Address: Wichita, Kansas License No.
Operation Completed: Hour 10PM Day 2 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 300' circulated with cement - 4 1/2" 4541' with 250 sax cement - perf 4417'

Pulled 3000' 4 1/2" to 300', circulated hole with heavy mud, displaced 30 sax readymix cement through 4 1/2" at 300', heavy mud to 40', set plug, hulls and filled to bottom cellar with readymix cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/10/62
INV. NO. 5829-11