

1090951

TO: STATE CORPORATION COMMISSION

9-11

API NUMBER 15-025-20,971-30001
NE SW NE SEC. 29, T 32 S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 3570 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1729 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME VAN BLARICUM "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY CLARK

OPERATOR LICENSE # 31330

WELL TOTAL DEPTH 4920 159.90 FEET

OPERATOR: PETROFIELD SERVICES CORP PRODUCTION CSG: SIZE 5 1/2 " FEET 4865

NAME AND RR #5 BOX 104 SURFACE CASING: SIZE 8 5/8" FEET 828'

ADDRESS CHICKASHA, OK 73018

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PETROFIELD SERVICES CORP LICENSE NUMBER 31330

ADDRESS RR #5 BOX 105, CHICKASHA, OK 73018

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 11 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ED LIVLEY

(COMPANY NAME) PETROFIELD SERVICES CORP (PHONE) 405-224-1113

WERE: PERFS AT 4696-4699

1ST PLUG SPOT 25 SX CEMENT AND 300# HULLS THROUGH TUBING AT 4860'. PULL TUBING OUT OF HOLE. 2ND PLUG PULL CASING TO 1200', SPOT 40 SX CEMENT. 3RD PLUG PULL TO 850' SPOT 50 SX CEMENT, 4TH PLUG PULL TO 450' SPOT 20 SX CEMENT, 5TH PLUG PULL TO 40' CIRCULATE 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 11 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 25 SX CEMENT AND 300# HULLS THROUGH TUBING AT 4860'. PULL TUBING OUT OF HOLE. 2ND PLUG PULL CASING TO 1200' SPOT 40 SX CEMENT, 3RD PLUG PULL TO 850' SPOT 50 SX CEMENT, 4TH PLUG PULL TO 450' SPOT 20 SX CEMENT, 5TH PLUG PULL TO 40' CIRCULATE 15 SX CEMENT.

REMARKS: CLASS "A" CEMENT BY PETROFIELD. RECOVERED 4020' OF 5 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE SEP 17 1998

SIGNED (TECHNICIAN) FORM CP-2/3

INV. NO. 51317

RECEIVED KANSAS OIL & GAS COMMISSION SEP 15 1998 09-15-98