

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

5-9

2-040880

API NUMBER: 15-077-20,201 0000

C NE NW , SECTION 12 TOWNSHIP 33 RANGE 7W

OPERATOR LICENSE # 4549 4620 FEET FROM S SECTION LINE
OPERATOR ANADARKO PETROLEUM CORPORATION 3300 FEET FROM E SECTION LINE
NAME & P.O. BOX 351
ADDRESS LIBERAL, KS 67905
LEASE NAME: HAYTER "A" #1
COUNTY: HARPER 146.02
WELL TOTAL DEPTH: 4493'
PIPE: 4 1/2" @ 4477
SURFACE CASING: 8 5/8" @ 284'

ABANDONED OIL WELL _____ GAS WELL INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SARGENT & HORTON PLUGGING INC

ADDRESS: RR 1, BOX 49BA, TYRONE, OK 73951 LICENSE: 31151

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: KIRBY

COMPANY NAME: SARGENT & HORTON PLUGGING INC PHONE: (405) 854-6515

WERE: 20 SACKS AT 4450'

REC PIPE

35 SACKS 1170' CIRC 320'- 0'

35 SACKS AT 780'

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()


COMPLETED: HOUR: 15:00 DAY: 9 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: 20 SACKS OF CEMENT TO 4400'. RECOVERED 4 1/2" FROM 3624'. PULLED TO 1170', SPOTTED 35 SACKS. PULLED TO 780', SPOTTED 35 SACKS OF CEMENT. PULLED TO 320' AND CIRCULATED CEMENT TO SURFACE.

REMARKS: 190 SACKS CEMENT STAR LUMBER, ALVA, OK

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.


STEVE VAN GIESON

MAY 13 1997

FORM CP-2/3

CONSERVATION DIVISION
WICHITA, KS

REV. 3/90

INVOICED

DATE MAY 14 1997

INV. NO. 48106

5-9