

6040826

12-10 15:051:05254.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1941

NE NW SE, SEC. 14, T. 11 S, R. 18 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Operator: Kaiser Francis Oil Co.

Name & Address: Box 666

Ellinwood, Kansas 67526

Lease Name Lynn Well # 3

County Ellis 111.41

Well Total Depth 3428 feet

Conductor Pipe: Size 16" feet 91' w/150 sks

Surface Casing: Size 10 3/4 feet 1131' w/400 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Kansas

Company to plug at: Hour: Day: 10 Month: Dec Year: 19 87

Plugging proposal received from John Glenn

(company name) Kaiser Francis (phone)

were: 4 1/2" casing set at 3426' w/150 sks cement. T.O.C. 2776' temp survey;

Open hole: ran W.L.M. to 3386' bottom sanded off; ran boiler to cement bottom, hung up at 1236'; Perf 4 1/2" casing at 1130' w/3 shots and perf Dakota at 595' w/3 shots;

Ordered 350 sks 65/35 Poz 10% Gel w/1/4# Flocele per sk plus 8 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15PM Day: 10 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT

Perf 4 1/2" casing at 1130' w/3 shots, perf base Dakota at 595' w/ 3 shots.

Pumped in 4 1/2" casing, 75 sks cement w/1/4# Flocele followed w/200 sks cement w/1/4#

Flocele plus 8 sks Hulls. Max 1200# S.T. 700#.

RECEIVED STATE CORPORATION COMMISSION

JAN 18 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 1-20-88

INV. NO. 19600

Signed Dennis L. Hamel (TECHNICIAN) Dennis Hamel