

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-19447-0001

~~NE~~, Sec. 14, T 11 S, R 18 ~~W~~E

1980 feet from ~~N~~S section line

1650 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Hugh Well # 3

Operator: Phillips Petroleum Co.  
Name & Address: Box 287, Great Bend, Ks 67530

County Ellis

Well Total Depth 3410 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 1150'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 176, Chase, Ks. 67524

Company to plug at: Hour: 10:00 AM Day: 13 Month: 1 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Frea

(company name) Phillips Petroleum Co. (phone) \_\_\_\_\_

were: Order 165 lbs. 50% osmix - 4? gal. - 3% cal. l., 5 lbs. hulls, 15 lbs. Gel. + 8 5/8" plug.

Signed Guth G. Schel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 PM Day: 13 Month: 1 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 1150' SP. cas. w/ 350 lbs. common, 5 1/2" set at 3406' w/ 200 lbs. common. 4 1/2" liner set from 3370' to 3478' w/ 20 lbs. cement. Top perf. at 3128'. P.B. to 3370'. Plugged bottom w/ 5 lbs. cement, sand + 5 lbs. cement to 3050'. Shot pipe 2 times + recovered 1800'. Pumped in 8 5/8" SP, 4 lbs. hulls, 12 lbs. Gel., 65 lbs. cement, 3 lbs. Gel., 1 lb. hulls, released plug + followed w/ 100 lbs. cement.

Remarks: Maximum pressure 1500 pounds.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

STATE CORPORATION COMMISSION

JAN 31 1983

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED Guth G. Schel  
(TECHNICIAN)

DATE 2-8-83

INV. NO. 2380-W

FORM CP-2/3  
Rev. 9-82