

4-041530

11-3

15-05105250-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 7-20-1911

SW NE NE /4 SEC. 14, 11 S, 18 W
4290 feet from S section line
990 feet from E section line

Operator license# 3252

Lease Diane well # 2

Operator: Venture Resources

County Ellis

Address: 518 - 17th Street
Suite #1130
Denver, CO 80202

Well total depth 3375 feet
Conductor Pipe: 13 inch @ 79 feet
Surface pipe 8 5/8 Inch @ 1130 feet
w/325 sx.

109.68

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 3 Month: November Year: 93

Plugging proposal received from: Herman Fellhaelter

Company: H & C Inc. Phone:

Were: 4 1/2" casing set @ 3360' w/100 sx. cement. O.H. @ 3360'-3375'.
Anhy. @ 1130' - Dakota @ 520' - T.O.F. @ 1400'. Tubing fish - 750'
of tubing on bottom.

Ordered 275 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 6:00P.M., Day: 3, Month: November, Year: 93

Actual plugging report: 11-3-93 - Plug bottom with 100 sx. 60/40 pozmix
10% gel with 1/4# F.C. plus 300# hulls. Push wiper plug to 1980'.

11-04-93: W.L.M. top cement @ 982'. Cut off casing @ 980'. Spot
50 sx. cement thru casing @ 980'. Pull to 550' circulate cement to
surface with 75 sx. Pull casing and fill to surface with 10 sx.
cement. Fluid circulated from holes @ 1733' to surface with 100 sx.
cement at bottom.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

I did X / did not] observe the plugging.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE NOV 23 1993

INV. NO. 39308

(agent)

Form CP-2/3

NOV 17 1993

CONSERVATION DIVISION
Wichita, Kansas