

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05249-00-00
Spot: CNENENE Sec/Twnshp/Rge: 14-11S-18W
330 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: DEANE Well Number: 1
County: ELLIS Total Vertical Depth: 3368 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2110 S. GILPIN PO BOX 101234
DENVER, CO 30250

Conductor Pipe: Size 13 feet: 74
Surface Casing: Size 8.625 feet: 1130 325 SX CMT
Production: Size 4.5 feet: 3357 100 SX CMT
Liner: Size feet:

109.46

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/07/2002 12:30 PM

Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC

Proposal Rcvd. from: RON MACKEY Company: VENTURE RESOURCES, INC. Phone: (303) 722-2899

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 700# hulls on 11-07-2002.
Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls on 11-12-2002.
Open hole 3357' - 3368'.
4 1/2" was squeezed on 03-08-2002, 03-09-2002, 03-11-2002, & 03-14-2002 by Allied Cementing Company.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/12/2002 1:15 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing Company tied onto casing and pumped 160 sxs mixed with 700# hulls into casing. Well went on vacuum.
Tied onto backside - pumped 10 sxs with Max. P.S.I. 350#. S.I.P. 300#.
Tied back onto casing and pumped 30 more sxs cement.
Let well set until 11-12-2002. Well was 23 seconds to fluids.
11-12-2002 - Dropped rock - well was 6 seconds to metal surface.
Allied tied onto casing and pumped water to 1000# before metal object moved and was able to pump into formation.
Allied ran wireline to 1175'.
Allied tied back onto casing and pumped 100 sxs 60/40 pozmix with 500# hulls.
Max. P.S.I. 100#. S.I.P. 0#.
Let well set for 1/2 hour and topped casing with an additional 10 sxs cement.
Hole standing full of cement.
Job complete.

RECEIVED

NOV 18 2002

KCC WICHITA


Remarks: ALLIED CEMENTING COMPANY - TICKET#11462 AND #11693.

Plugged through: CSG

District: 04

job -

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 11-19-02

INV. NO. 2003060836

NOV 13 2002

130104M

701 2000 1.04

SHELL OIL CO

#1 DEANE

14-11-18W
NE NE NE

Contr.

ELLIS County

E 1863

Comm 6-4-41

Comp 7-9-41

IP

3000 BOPD

Tops	Depth	Datum	Casing
			15" 75
			8" 1129
			4" 3357
CONG	3325		
SDP	3337		
ARB	3356		
TD	3360		

DEPTH

A/500: Swb 200 EO/3 hrs

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

1/A