

TO: 1060159
STATE CORPORATION COMMISSION

5-11

API NUMBER NA 15-135-70386-0000
SW SE SEC. 23, T 19 S, R 24 W

CONSERVATION DIVISION - PLUGGING SECTION 6660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BOYD WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY NESS 141.25

OPERATOR LICENSE # 6622 WELL TOTAL DEPTH 4346 FEET

OPERATOR: JASON OIL PRODUCTION CSG: SIZE 5 1/2" @ 4342' WITH 125 SX

NAME AND PO BOX 701 SURFACE CASING: SIZE 8 5/8" @ 278' WITH SX

ADDRESS RUSSELL, KS 67665

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR HEMBREE WELL SERVICE LICENSE NUMBER 32066

ADDRESS PO BOX 458, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 11 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) HEMBREE WELL SERVICE (PHONE) 785-798-3408

WERE: DV TOOL @ 1585 WITH 425 SX CEMENT

1ST PLUG PUMP 50 SX CEMENT AND 300# HULLS AT 3236'. COULDN'T GET BIT OR TUBING BELOW 3167' HITTING CASING. 2ND PLUG PULLED TUBING TO 1600' AND MIXED 70 SX CEMENT. 3RD PLUG PULLED TO 400' THEN MIXED 60 SX CEMENT AND CIRCULATED. WENT DOWN BACK SIDE WITH 20 SX CEMENT. PRESSURED TO 500# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 11 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG PUMPED 50 SX CEMENT AND 300# HULLS AT 3236'. COULDN'T GET BIT OR TUBING BELOW 3167' HITTING CASING. 2ND PLUG PULLED TUBING TO 1600' AND MIXED 70 SX CEMENT. 3RD PLUG PULLED TO 400' THEN MIXED 60 SX CEMENT AND CIRCULATED. WENT DOWN BACK SIDE WITH 20 SX CEMENT. PRESSURED TO 500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. RECEIVED COMMISSION SIGNED Michael Maier / MP

DATE 6-3-99 MAY 26 1999 (TECHNICIAN) FORM CP-2/3

INV. NO. 61002 CONSERVATION DIVISION Wichita, Kansas